



Firmware Version: 2.10rc036

Published Date: 2016/03/23

Content:

Upgrading Instructions:..... 2
 Upgrading by using Web-UI..... 2
New Features:..... 3
Changes of MIB & D-View Module:..... 3
Problems Fixed: 3
Known Issues: 3
Related Documentation: 3

Revision History and System Requirement:

Firmware Version	Date	Model	Hardware Version
2.02rc019	2014/12/22	DAP-2310	B1
2.06rc029	2015/07/06		
2.07rc031	2016/03/23		

Upgrading Instructions:

D-Link AP supports firmware upgrading via Web-UI. You may download the firmware from D-Link web site <http://tsd.dlink.com.tw>.

Upgrading by using Web-UI

1. Connect a work station to the LAN port of Access Point.
2. Open the web browser of work station and entering the IP address of the AP. The system default IP address is 192.168.0.50.
3. Enter administrator's username and password, user name is "admin" and leave the password field blank by default.

To update the AP's firmware, click **Maintenance > Firmware and SSL Certification Upload**

The screenshot shows the D-Link Web-UI interface for a DAP-2310 device. The top navigation bar includes Home, Maintenance, Configuration, System, Logout, and Help. The left sidebar shows a tree view with DAP-2310, Basic Settings, Advanced Settings, and Status. The main content area displays the 'System Information' page with the following details:

Model Name	DAP-2310
Firmware Version	2.10 17:16:37 07/13/2016
System Name	D-Link DAP-2310
Location	
System Time	09/21/2016 17:33:29
Up Time	30 Days, 6:36:15
Operation Mode	Access Point
MAC Address	c4:a8:1d:91:b1:10
SSID 1~7	c4:a8:1d:91:b1:11 ~ c4:a8:1d:91:b1:17
IP Address	192.168.0.205

New Features:

None

Changes of MIB & D-View Module:

1. Support CWM v1.03
2. Support Captive portal with Multiple SSID and VLAN
3. Captive portal support https URL redirect
4. Display station's OS in client information for Captive portal client
5. One SSID with multiple schedule settings
6. MAC ACL from per SSID 64 to per radio share 512
7. Support External captive portal in CWM mode
8. Country selection for specific country code

Problems Fixed:

Firmware Version	Problems Fixed
V2.10	<ol style="list-style-type: none"> 1. Fix if enable WLAN partition, blocking access from LAN to WLAN, clients does not get IP address and not have network access. 2. Fix DBG16060127->Disable AP array if cwm is enabled. 3. Fix DBG16070013->IPv6 without need authentication could connect to internet

Known Issues:

Firmware Version	Known Issues
V2.10	None

Related Documentation:

- DAP-2310 User Manual v2.04(WW&US)